BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PM1/052/2012-13 Dated: 21-01-2013

APPROVED TENDER SCHEDULE --'B'

Item No: 75

Name of Work:-Providing chain link fencing to open space in 'B' sector in ward No 04 of YST sub Division

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri M B HONNAL	
				Rate	Rate in Words
1	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification. specification	Cum	97.67	80.00	Rupees eighty and paise zero only
2	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and	Cum	480.38	120.00	Rupees one hundred twenty and paise zero only
3	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 7.5 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specifiation with all lead and lift complete asper specification as per direction of Engineer incharges	Cum	15.30	4000.00	Rupees four thousand and paise zero only
4	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	45.90	2500.00	Rupees two thousand five hundred and paise zero only
5	KSRB 5.3-2 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chisile dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications	Cum	28.05	3200.00	Rupees three thousand two hundred and paise zero only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri M B HOMBAL	
				Rate	Rate in Words
6	KSR13-4-1.6 : Providing and laying in position plain cement concrete of mix M 15 withOPC cement @ 240kgs. with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification	Cum	35.20	4600.00	Rupees four thousand six hundred and paise zero only
7	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm	136.00	70.00	Rupees seventy and paise zero only
8	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead and lift and as per the directions of the Engineer-in-charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting. (excluding cost of earth work and concrete)	Mtr	362.60	700.00	Rupees seven hundred and paise zero only
9	Providing chain link fencing 50mm size of 8 guage properly stretched between rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts, cutting, bending wherever necessary, wastage and lapping etc complete as per direction of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint.(	Sqm	621.00	550.00	Rupees five hundred fifty and paise zero only
10	Providing and fixing M.S. Black pipe of 38mm dia, of heavy guage of 14 including removing the hends, cutting the pipe, and fixing pipe in between the two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. black pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint	Mtr	828.00	245.00	Rupees two hundred forty five and paise zero only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor for Approved Rates Sri.M B HOMBAL	
				Rate	Rate in Words
11	Providing and fixing M.S Gate as per Cheaf Architect Drawing using 50mmX50mm 14 guage M.S hollow pipe frame work bent to ornamental shape as shape as shown in the drawing and 35mmX6mm and 16X16mm squre rods for verticals alternatively spaced at 4cms c/c in two halves and 40mmX6mm M.S flats for horizontal member and at at the top cast iron spikes are provided at alternate vertical members as shown in the drawing etc., complete. All the steel surface should be thoroughly cleaned free of of rust and painted with anti corrosive paint (shop paint) etc., complete the work includes cost of all materials, labour charges for all item of work, hire charges of welding, cutting and grainding equipment, and electricity charges, with lead and lift loading and lunloading charges. etc., complete as per specification and drawing	Sqm	15.00	2400.00	Rupees two thousand four hundred and paise zero only
12	Lead for Disposal of Debris shall be payable at carrage rates by Mechanical means inleuding loading and unloading for 7.00 Km with all lead and lift complete as per specification as per direction of Engineer incharges.	Cum	480.38	80.00	Rupees eighty and paise zero only

Signature of the Contractor

Executive Engineer,
Yelahanka Division
BBMP, Bengaluru-64